



INSPECTION SERVICES FOR THE CITY AND  
CAMROSE COUNTY

PERMIT NO.

PRIVATE SEWAGE TREATMENT SYSTEM PERMIT

Date: \_\_\_\_\_ Municipality \_\_\_\_\_ Roll # \_\_\_\_\_ Zone \_\_\_\_\_

Permit Applicant: ☐ Owner ☐ Contractor

Owner Name \_\_\_\_\_ Mailing Address \_\_\_\_\_

City \_\_\_\_\_ Province \_\_\_\_\_ Postal Code \_\_\_\_\_ Phone \_\_\_\_\_

Cell \_\_\_\_\_ Email \_\_\_\_\_ Fax \_\_\_\_\_

Contractor/Firm Name \_\_\_\_\_ Mailing Address \_\_\_\_\_

City \_\_\_\_\_ Province \_\_\_\_\_ Postal Code \_\_\_\_\_ Phone \_\_\_\_\_

Cell \_\_\_\_\_ Email \_\_\_\_\_ Fax \_\_\_\_\_

Project Location Street/Rural Address \_\_\_\_\_

Lot \_\_\_\_\_ Block \_\_\_\_\_ Plan \_\_\_\_\_ Section \_\_\_\_\_ Township \_\_\_\_\_ Range \_\_\_\_\_ W4

INSTALLATION DETAILS

TYPE OF OCCUPANCY	TYPE OF WORK	INSTALLATION	TREATMENT DISPOSAL METHODS
<input type="checkbox"/> Single Residential <input type="checkbox"/> Commercial <input type="checkbox"/> Industrial <input type="checkbox"/> Offsite Manufactured Home <input type="checkbox"/> Shop <input type="checkbox"/> Accessory Building <input type="checkbox"/> Other:	<input type="checkbox"/> New <input type="checkbox"/> Renovation <input type="checkbox"/> Subdivision <input type="checkbox"/> Other:	<input type="checkbox"/> New <input type="checkbox"/> Alteration Expected Volume of Effluent: <input type="checkbox"/> m <sup>3</sup> /day _____ <input type="checkbox"/> litres/day _____ <input type="checkbox"/> gallons/day _____ (not to exceed 25 m <sup>3</sup> /day) # of bedrooms: _____ (residential including basement and future development)	<input type="checkbox"/> Septic Tank <input type="checkbox"/> Holding Tank <input type="checkbox"/> Treatment Mound <input type="checkbox"/> Treatment Field <input type="checkbox"/> Open (Surface) Discharge <input type="checkbox"/> Packaged Sewage Treatment Plant <input type="checkbox"/> At-Grade <input type="checkbox"/> Privy <input type="checkbox"/> Other:

**FOIPP Notification:** The personal information required by the City of Camrose application forms is collected under the authority of section 33(c) of the Alberta Freedom of Information and Protection of Privacy Act and will be protected under Part 2 of that Act and section 63 of the Safety Codes Act. It will be used for processing permit applications, issuing permits, safety codes compliance monitoring and verification. The name of the permit holder and nature of the permit may be included on reports provided to a municipality or made available to the public as required or allowed by legislation. Personal information may also be used by the city of Camrose to conduct ongoing evaluations of the services provided by its service providers to permit applications, permit holders and owners. Please direct any questions about this application to the City of Camrose FOIPP Coordinator at 780.672.4426.

Certified Installer's Name (Print) \_\_\_\_\_

Certified Installer's Signature \_\_\_\_\_

Homeowner Signature (**homeowner permit only**) \_\_\_\_\_

By signing this application I hereby certify that I own or will own and occupy this dwelling.

Certified Installer's PS# \_\_\_\_\_

Office Use Only

Permit Fee	SCC Levy (\$4.50 or 4% of permit fee, max \$560.00)	Issuer's Name
Travel Fee (Includes GST)	Total Cost	Issuer's Signature
Credit Card No.:	Receipt No.	Designation Number
	Expiry:	Permit Issue Date
	SCO Designation No.	SCO Signature

Permit expires two years after Permit Issue Date unless, prior to expiry date, an extension is applied for and accepted at the Discretion of the Safety Codes Officer.

# Private Sewage Treatment System

The following information will be required when submitting an application for a private sewage treatment system permit.

## Site plan

Location of all buildings/proposed buildings and improvements

Location of well/cistern and any sloughs or waterways, water courses and property lines.

## Septic tank, sewage holding tanks or sewage effluent tanks shall not be located within

- a) 10 m (33 ft.) of a water source or water well,
- b) 10 m (33 ft.) of a water course,
- c) 1 m (3.25 ft.) of property line, and
- d) 1 m (3.25 ft.) of a building

## Open Discharge

- 1) An open discharge system may be installed in a location that provides separation distances from the point of discharge of not less than
  - a) 50 m (165 ft.) to a water source includes water well, and or cistern
  - b) 100 m (330 ft.) from a licensed municipal water well
  - c) 45 m (150 ft.) to a water course except as required by Article 2.1.2.4.
  - d) 90 m (300 ft.) to a property line, and
  - e) 45 m (150 ft.) to a building.

- 2) The effluent discharge piping shall be buried to at least the point where the separation distances set out in Sentence (1) are met.

## Treatment Fields

- 1) A treatment field, measured from any part of a weeping lateral trench, shall not be located within
  - a) 15 m (50 ft.) of a water source or water well,
  - b) 100 m (330 ft.) of a licensed municipal water well,
  - c) 15 m (50 ft.) of a water course, except as provide in Article 2.1.2.4,
  - d) 1.5 (5 ft.) of a property line,
  - e) 10 m (33 ft.) from a basement, cellar, or crawl space, <sup>1</sup>
  - f) 1 m (3.25 ft.) of a building that has a permanent foundation but does not have a basement, cellar or crawl space, and
  - g) 5 m (17 ft.) from a septic tank or package sewage treatment plant.

<sup>1</sup> Note: Clause (1)(d) – The 10m (33 ft.) requirement to a basement, cellar, crawl space is intended to protect excavations below grade from accumulating migrating effluent. A crawl space that is not below grade, or where the level of the ground surface at the soil based treatment area is below the level of the crawl space the separation required is 5 m (17 ft.) clearance, as it can be treated as a building without a basement.

## Treatment Mounds

- 1) A treatment mound shall not be located within
  - a) 15 m (50 ft.) of a water source or water well,
  - b) 100 m (330 ft.) from a licensed municipal water well
  - c) 15 m (50 ft.) of a water course, except as provided in Article 2.1.2.4.
  - d) 3 m (10 ft.) of a property line,
  - e) 3 m (10 ft.) of a septic tank,
  - f) 10 m (33 ft.) of a basement, cellar or crawl space, and
  - g) 10 m (33 ft.) of a building that does not have a basement, cellar, or crawl space.

# Private Sewage System Design Example/Template

## Field

### PREFACE

(Version April 1, 2011)

This is an example design document for a septic tank and treatment field system. It reflects the information needed to demonstrate the design considerations for the particular site and system required by the Private Sewage Standard of Practice 2009 (Standard) have been made. Considerations needed for a particular site may go beyond those used as an example in this document.

This example document can be used as a template by editing or adding critical information to suit the particular site and system. This is an example only.

While it is preferable to use a consistent format to facilitate quick review, other formats of the design may be accepted by the Safety Codes Officer (SCO), if the design includes the required information that shows the necessary design considerations were made.

A design is required in support of a permit application. It includes drawings and supporting information as it applies to the specific design. This is the information a SCO will review to evaluate whether design considerations required by the Standard have been adequately made prior to issuing the permit.

Including the design in the operation and maintenance manual that must be provided to the owner, will simplify development of the operation and maintenance manual.

# PRIVATE SEWAGE SYSTEM DESIGN CONSIDERATIONS AND DETAIL.

Joe Smith  
Box 1,  
Somewhere, Alberta

**Legal Description of Property:**

SE Sec 9, Twp 71, Rge. 5, W of 6 Mer.  
Lot 1; Blk 1; Plan 123450

**Municipal Address:**

19035 - Rge. Rd. 5

This private sewage system is for a 4-bedroom single family dwelling. The total peak wastewater flow per day used in this design is 461 imperial gallons. The average operating flow is expected to be 300 gallons per day.

The sewage system includes a septic tank and treatment field system. This system is suitable for the site and soil conditions of your property. The design reflected in the following applies, and meets, the requirements of the current Alberta Private Sewage Systems Standard of Practice (Standard). The system will achieve effective treatment of the wastewater from this residence.

## 1 Wastewater Characteristics

### 1.1. Wastewater Peak flow

The development served is a 4-bedroom single-family dwelling. Based on the characteristics of the home identified during the review the total plumbing fixture unit load in this residence is 21. This requires 11 Imp. gal/day be added to the peak daily flow. Fixture unit load is as follows:

- Main bath = 6 fixture units
- Bathroom with shower off master bedroom = 6 fixture units
- Kitchen sink = 1.5 fixture units
- Laundry stand pipe = 1.5 fixture units
- Bathroom in basement = 6 fixture units

<b>Total peak daily flow used in the design is:</b> <b>450 Imp. gal + 11 Imp. gal = 461 Imp. gal</b>
---

<b>461 Imp. gal/day</b>
-------------------------

### 1.2. Wastewater Strength

Characteristics of the development were considered to assess sewage strength. No garbage grinders or other characteristics were identified that would cause typical wastewater strength to be exceeded.

<b>Projected wastewater strength for the design is:</b>
---

<b>BOD 220 mg/L</b> <b>TSS 220 mg/L</b> <b>Oil and Grease 50 mg/L</b>
---

### 1.3. Wastewater Flow Variation Considerations

The characteristics of this development indicate wastewater flow volumes will not vary substantially during the day or from day to day. As a result, no flow variation management is needed.

## 2 Site Evaluation Findings

### 2.1 Site Evaluation

The lot is 3.88 acres (1.57 hectares). The dimensions of the property are shown in the drawing attached in Appendix A. The adjacent land use is country residential development, varying in size from approximately 1.5 to 3 hectares. There is a water well and a treatment mound on the neighbouring property to the north and south.

Blueberry Creek runs parallel to the southwest property line. The southwest portion of the property has a 5% slope toward the creek. Seasonally saturated soils were found in the lower slope areas near the southwest property line. Line locates confirmed there are no existing utilities in the area selected for the system components. **The area selected for the system must be kept clear of any utilities to be installed.** No utility right-of-ways or easements were noted on the subject site based on a review of the survey plan attached to this design and as indicated by the owner.

The site evaluation assessed the area within in 330 ft (100 m) of all system design components. The selected treatment site is nominally flat. No significant setback constraints were noted. Pertinent features identified during the site review and the required setback distances are identified on the site plan in Appendix A.

### 2.2 Soils Evaluation

Three soil test pits were investigated on this site. Test Pit 1 is located where the owner preferred the system be located. This area has severe soil constraints requiring a treatment mound at more expense; however, this area could act as a back up if needed. Test pits 2 and 3 identified better soil characteristics suitable for the installation of a treatment field receiving effluent from a septic tank.

There is little variability between test pits 2 and 3 so they are adequate for design purposes. The location of the test pits are shown on the site plan in Appendix A. Soil profile descriptions of each test pit are attached in Appendix B.

## 3 Key Soil Characteristics and Effluent Loading Rates

### 3.1. Restrictive Layer Considerations

A restrictive layer exists at 7 feet below surface as indicated by:

- redoximorphic features – mottling at 7 ft; gleying below 7.5 ft,
- saturated, sandy clay textured soil having massive structure at 7.5 feet will severely limit downward flow.

### 3.2. Limiting Condition For Soil Loading Rate Selection

The key soil characteristic affecting effluent loading is:

- **Fine Sandy Loam (FSL) textured soil having a blocky, grade 3 structure at the depth of 24 to 60 inches.**

### 3.3. In Situ Soil Effluent Loading Rate Selection

- **effluent loading rate for primary treated (septic tank) effluent on this soil is 0.32 Imp. gal/day/ft<sup>2</sup>.**

### **3.4. Effluent Linear Loading Rates and Design Considerations**

The soil profile characteristics do not require the application of linear loading rates set out in the Standard. However, this design minimizes linear loading as the laterals have been oriented to make the field long and narrow and at 90 degrees (perpendicular) to the assumed direction of the underlying ground water flow toward the creek to the southwest.

The trench bottom depth of this treatment field will be at a maximum of 2 feet below surface. For this level site the trench bottom elevation for the 5 weeping lateral trenches are the same.

## **4 Initial Treatment Component Design Details**

Details of the initial treatment components required for this design are attached in Appendix C.

### **4.1 Septic Tank and Dose Tank**

Details of the initial treatment components required for this design are attached in Appendix C.

#### **4.1 Septic and Dose Tank Requirements**

##### **4.1.1 Septic Tank**

**The working capacity of the septic tank specified for this design is 1218 Imperial gallons.** Appendix C includes specifications for septic tank Model ST 1218.

The minimum working capacity based on Table 4.2.2.2 of the 2009 SOP for this development is 951 Imp. gal [940 Imp. gal/day plus the additional flow of 11 Imp. gal].

Burial depth of the septic tank at finished grading above the top of the tank will be 4ft 6 inches. This tank is rated for a maximum burial depth of 5 ft 10 inches. Insulation of the tank is not required as the burial depth exceeds 4 feet.

##### **4.1.2 Dose Tank**

The dose tank (second chamber) has a total capacity of 670 Imp. gal. In addition to the single dose volume the tank provides approximately 220 Imp. gal emergency storage above the high effluent alarm setting. Specifications provided by the manufacturer are shown in Appendix C.

##### **4.1.3 Effluent Filter**

An inline 2-inch diameter Sim/Tech<sup>®</sup> model STF-100 effluent filter having an effective opening of less than 1/8-inch (3.2 mm) is used. When clean the filter is rated at a head loss of 0.5 feet at a flow of 80 Imp. gal/min. A one year service interval is expected with typical flow volumes and wastewater characteristics.

## **5 Soil Treatment Component Design Details**

### **5.1 Selection of Soil Infiltration System Design**

The system selected for this design is a septic tank and treatment field using 22 inch wide chambers and pressure distribution of effluent. To maintain the required 5 foot vertical separation to the restrictive layer identified in the soil profile the maximum depth of the trench bottom is 2 feet below grade.

## 5.2 Treatment Field Size

Trench bottom area:

Expected peak daily flow:	461 Imp. gal/day
Soil loading rate:	0.32 Imp.gal/day/ft <sup>2</sup>
<b>Trench bottom soil infiltration surface area:</b>	<b>1441 ft<sup>2</sup></b>

The 22 inch chambers receiving primary treated effluent Level 1 that is spread over the trench bottom surface area using pressure distribution receives a 1.3 width credit, resulting in a credited trench bottom soil infiltration width of 2.38 feet.

Total length of trench bottom required: 605 ft

Layout consists of:

5 weeping lateral trenches - each 120 feet long.

The location of the treatment field on the property and layout of the laterals and are shown in Appendix A and D. The treatment field sizing worksheets are provided in Appendix E.

## 6 Effluent Distribution Design Detail

### 6.1 Effluent Pressure Distribution

Five 120 ft centre fed pressure effluent distribution laterals are used over the soil infiltration area. The calculations are provided in Appendix E on the pressure distribution worksheets. The pressure distribution lateral layout drawing is included in Appendix D.

#### 6.1.1 Effluent Pressure Distribution Lateral Design

The distribution laterals are center fed resulting in ten 60 ft pressure distribution laterals.

- Each lateral is 1-inch schedule 40 PVC pipe.
- Each lateral has 12, 1/8-inch orifices drilled at 5 foot spacing.
- The laterals shall be installed to maximize the elevation above the soil infiltration surface and exceed the minimum 4 inches above the soil infiltration surface.
- Pressure distribution lateral piping will be supported at a maximum of 4 foot spacing.
- All orifices shall point up except every 4<sup>th</sup> orifice shall point down and be equipped with an orifice shield.

The design achieves a minimum 5 foot pressure head at each orifice, resulting in a design flow of 0.34 Imp. gal/min from each 1/8-inch orifice.

There are 120 orifices throughout the effluent pressure distribution system resulting in a **total flow of 40.8 Imp gal/min**. An additional 3.3 Imp. gal/min is added for the ¼ inch drain back orifice drilled at the lowest elevation of the effluent piping in the dose tank to achieve drain back of the laterals and supply piping.

**Total flow from all orifices for this effluent pressure distribution system is 44.1 Imp. gal/min (53 U.S. gal/min).**

#### 6.1.2 Pressure Head Requirements

The total length of supply piping from the pump to the start of the pressure distribution laterals is 205 feet. The supply piping is 2 inch Schedule 40 PVC pipe. The allowance for equivalent length of pipe due to fittings is 69 feet of pipe. Total equivalent length of pipe is 274 feet. This is detailed in appendix E.

**Pressure head loss due to friction**

The friction loss through the piping at the flow of 40.8 Imp. gal/min is 10.1 feet of head pressure.

Other friction loss considerations required include:

- Allowance for head loss through the effluent filter under partial plugging is 5.5 feet.
- Allowance for pressure head loss along the pressure distribution laterals of 1 foot.

**Total pressure head required to overcome friction loss is 16.6 feet pressure head.**

**Pressure head to meet vertical lift requirements include:**

- A pressure head at each orifice of 5 feet.
- Lift distance of effluent from the low effluent level in the tank to the pressure distribution laterals is 7 feet.

Vertical lift and friction loss results in a **total pressure head** requirement of **28.6 ft.**

**Pump specifications:**

Demands for this pressure distribution lateral system are **44.1 Imp. gal/min (53 U.S. gal/min)** at **28.6 feet** of pressure head.

The pump capacity must exceed these demands to allow for variations in the design and decreased pump performance over time. A Myers model ME 50 effluent pump (1/2 hp) is specified for this system. The pump specifications with the effluent distribution system demands plotted on the pump curve are included in Appendix C.

**6.1.3 Effluent Dosing Volume and Control settings.**

The volume of effluent in the 600 ft of 1 inch PVC lateral piping is 22.4 Imp. gal. The volume of an individual dose must be at least 5 times the volume of the pressure distribution laterals, which is 112.2 Imp. gal.

The volume in the 205 ft of 2 inch PVC effluent supply line is 30.1 Imp. gal.

**Total individual dose volume** determining float settings is **142.3 Imp gal [30 Imp. gal to fill the effluent supply line and deliver the 112.2 Imp. gal per dose].**

**7 Controls**

All effluent level control floats will be attached to an independent PVC pipe float mast.

**7.1 Effluent Dosing Float Setting**

The dose tank dimensions result in 11.27 Imp. gallons per inch of depth. The float control elevations shall be set at:

- 12.5 inches between float off and on elevations (deliver 142.3 Imp. gal/dose).
- Off: 19 inches off floor of dose tank
- On: 31.5 inches off floor of dose tank

**7.2 High Liquid Level Alarm**

The high level alarm specified for this system is a JB Series 1000T (manufactured by Alarm Tech Inc.).

- Alarm control float is set at 1.5 inches above pump on elevation or at 33 inches above the floor of the dose tank/chamber.



## **8 Operation Monitoring Components**

The following components are included in the system design. See detailed drawings in Appendix D for locations.

### **8.1 Monitoring Ports**

Monitoring ports are provided at both ends of the sand layer to enable inspection of the effluent ponding depth that may result.

### **8.2 Pressure Distribution Lateral Clean Outs**

Clean outs are provided at the end of each pressure distribution lateral with access to grade through an access box suitable for its purpose and anticipated traffic.

### **8.3 Sampling Effluent Quality**

Samples of the effluent can be taken from the effluent dose chamber.

## **9 System Setup and Commissioning**

- Clean the septic tank and effluent chamber of any construction debris.
- Flush effluent distribution laterals.
- Conduct a squirt test to assess that residual head pressure required by the design is achieved and that the volume from each orifice is within allowed tolerances.
- Confirm the correct float levels and ensure this delivers the dose volume required by this design.

## **10 Operation and Maintenance Manual**

The Owner's Manual detailing the design, operation, and maintenance of the installed system will be provided to the owner in accordance with Article 2.1.2.8 of the Standard.

**Signature and closing by the designer/Installer.**

### **Attachments:**

- Appendix A – Site Information [Site Plan, Property Subdivision Plan]**
- Appendix B – Soil Information [Soil Profile Logs, Laboratory Analysis Results]**
- Appendix C – Manufacturer's and Design Specifications for System Components**
- Appendix D – Detailed System Schematics and Drawings**
- Appendix E – System Design Worksheets**

This design has been developed by (name of certified person and company name). This design meets the requirements of the Alberta Private Sewage Systems Standard of Practice 2009 unless specifically noted otherwise and in such case special approval is to be obtained prior to proceeding with installation of this design. *(Carry on with any other qualifications or limitations that in your opinion as the designer/installer are needed.)*

# Appendix A – Site Information

Joe Smith – SE Sec 9; Twp 71; Rge 5; W6M

May 31, 2011





Figure A1 – Subdivision Plan

# Appendix A – Site Information

Joe Smith – SE Sec 9; Twp 71; Rge 5; W6M

May 31, 2011



# Appendix B - Alberta Private Sewage Treatment System Soil Profile Log Form

## Smith Residence Soil Assessment

Legal Land Location						Test Pit GPS Coordinates			
LSD-1/4	Sec	Twp	Rg	Mer	Lot	Block	Plan	Easting	Northing
SE	9	71	5	W6M	12	1	123450	65032	34507
Investigation Date: October 5 <sup>th</sup> , 2009.		Vegetation notes: Prairie grasses.		Overall site slope % Slope position of test pit:			Variable across site. 2%		
Test hole No. Test Pit #1		Soil Subgroup		Parent Material		Drainage		Depth of Lab sample #1	
								Depth of Lab sample #2	

Horizon	Depth (cm) (in)	Texture	Lab or HT	Colour	Gleying	Mottling	Structure	Grade	Consistence	Moisture	% Coarse Fragments
A	Surface to 8 in.	Loamy Medium Sand (LMS)	HT	Dark brown.	None.	None.	Single Grain	0		Moist	20%
B	8 to 45 in.	Fine Sandy Loam (FSL)	HT and Lab	Light brown.	None.	None.	Blocky	3	Friable	Moist.	10%
B	45 to 60 in.	Silt Loam (SIL)	HT	Light brownish grey.	At 4.5 ft saturated and gleyed.	4 to 5 ft many prominent distinct mottles noted throughout.	Prismatic	2	Friable to firm.	Moist to wet below 4.5 feet.	<1%
C	60 to 96 in.	Sandy clay (SC)	HT	Light to dark grey.			Massive	0	Firm	Moist to wet.	<3%

Depth to Groundwater	4.5 feet.	Restricting Soil Layer Characteristic		Sandy clay restricts downward effluent movement as massive and contains saturated conditions.	
Depth to Seasonally Saturated Soil	4 feet.	Depth to restrictive Soil Layer		4 feet.	
Site Topography	Slightly undulating.	Depth to Highly Permeable Layer Limiting Design		Not encountered in this soils assessment and design.	
Key Soil Characteristics applied to system design effluent loading	The grain size analysis conducted by the lab for this sample from 8 to 45 inches determined that the sand fraction in the Sandy Loam is fine grained. It is the key soil horizon for effluent loading design considerations.				
Weather Condition notes: Slightly overcast with moderate wind - no rain or other conditions that would impact soils assessment were encountered.					
Comments (such as root depth and abundance or other pertinent observations): This test pit location has limited suitability for an onsite sewage system. A treatment field is not acceptable because of less than 5 ft vertical separation. A treatment mound could be designed for this location if required.					

# Appendix B - Alberta Private Sewage Treatment System Soil Profile Log Form

## Smith Residence Soil Assessment

Legal Land Location						Test Pit GPS Coordinates			
LSD-1/4	Sec	Twp	Rg	Mer	Lot	Block	Plan	Easting	Northing
SE	9	71	5	W6M	12	1	123450	65024	34535
Investigation Date: October 5 <sup>th</sup> , 2009.		Vegetation notes: Prairie grasses.		Overall site slope % Slope position of test pit:				Variable across site. Nominally flat.	
Test hole No. Test Pit #2		Soil Subgroup		Parent Material		Drainage		Depth of Lab sample #1 30 - 36 in.	
								Depth of Lab sample #2	

Horizon	Depth (cm) (in)	Texture	Lab or HT	Colour	Gleying	Mottling	Structure	Grade	Consistence	Moisture	% Coarse Fragments
A	Surface to 24 in.	Loamy Medium Sand (LMS)	HT	Dark brown.	None.	None.	Single Grain	0		Moist	40%
B	24 to 60 in.	Fine Sandy Loam (FSL)	HT and Lab	Light brown.	None.	None.	Blocky	3	Friable	Moist to dry.	5%
B	60 to 84 in.	Silt Loam (SIL)	HT	Light brownish grey.	None.	None.	Prismatic	2	Friable to firm.	Moist.	<1%
C	84 to 96 at end of test pit.	Sandy clay (SC)	HT	Light to dark grey.	At 7.5 ft saturated and gleyed.	7 to 7.5 ft Many distinct prominent mottles.	Massive	0	Firm	Moist to wet.	<5%
Depth to Groundwater		7.5 feet.		Restricting Soil Layer Characteristic			Massive Structured Sandy Clay restricts downward effluent movement and creates saturated conditions.				
Depth to Seasonally Saturated Soil		7 feet.		Depth to restrictive Soil Layer			7 feet.				
Site Topography		Slightly undulating.		Depth to Highly Permeable Layer Limiting Design			Not encountered in this soils assessment and design.				
Key Soil Characteristics applied to system design effluent loading		The lab grain size analysis of the sand portion in the Sandy loam soil from 24 to 60 inches determined the sand fraction is fine grained. This is the key soil horizon the system design must use.									
Weather Condition notes: Slightly overcast with moderate wind – no rain or other conditions that would impact soils assessment were encountered.											
Comments (such as root depth and abundance or other pertinent observations): Preferred trench depth is 18 to 24 inch. Roots extend to 6 feet (very fine at that depth) indicating no obvious limiting characteristic in the soil.											

# Appendix B - Alberta Private Sewage Treatment System Soil Profile Log Form

## Smith Residence Soil Assessment

Legal Land Location					Test Pit GPS Coordinates			
LSD-1/4	Sec	Twp	Rg	Mer	Block	Plan	Easting	Northing
SE	9	71	5	W6M	1	123450	64964	34557
Investigation Date: October 5 <sup>th</sup> , 2009.		Vegetation notes: Prairie grasses.		Overall site slope % Slope position of test pit:		Variable across site. Nominally flat.		
Test hole No. Test Pit #3		Soil Subgroup		Parent Material		Drainage		Depth of Lab sample #1 35 to 45 in.
								Depth of Lab sample #2


Horizon	Depth (cm) (in)	Texture	Lab or HT	Colour	Gleying	Mottling	Structure	Grade	Consistence	Moisture	% Coarse Fragments
A	Surface to 22 in.	Loamy Medium Sand (LMS)	HT	Dark brown.	None.	None.	Single Grain	0		Moist	45%
B1	22 to 63 in.	Fine Sandy Loam (FSL)	HT and Lab	Light brown.	None.	None.	Blocky	3	Friable	Moist to dry.	5%
B2	63 to 84 in.	Silt Loam (SIL)	HT	Light brownish grey.	None.	None.	Prismatic	2	Slightly friable.	Moist to dry.	4%
C	84 to 96 in.	Sandy clay (SC)	HT	Light to dark grey.	At 7.5 ft is saturated and gleyed.	At 7 to 7.5 ft many prominent distinct mottles	Massive	0	Firm	Moist to wet.	<2%
Depth to Groundwater		7.5 feet.		Restricting Soil Layer Characteristic			Sandy clay restricts downward effluent movement as massive and contains saturated conditions.				
Depth to Seasonally Saturated Soil		7 feet.		Depth to restrictive Soil Layer			7 feet.				
Site Topography		Slightly undulating.		Depth to Highly Permeable Layer Limiting Design			Not encountered in this soils assessment and design.				
Key Soil Characteristics applied to system design effluent loading		The lab grain size analysis of the sand portion in the Sandy loam soil from 22 to 63 inches determined the sand fraction is fine grained. This is the key soil horizon the system design must use. Test pits 2 and 3 are consistent in their characteristics.									
Weather Condition notes: Slightly overcast with moderate wind – no rain or other conditions that would impact soils assessment were encountered.											
Comments (such as root depth and abundance or other pertinent observations): The sand particle size in the Sandy Loam soil of the B1 horizon as identified by lab tests is fine sand. This is the soil horizon most affecting design of the system with the preferred trench depth from 18 to 24 inches.											

## **(APPENDIX B)**

**Insert lab analysis results of soil samples taken  
for determining soil texture!**

## Appendix C - Manufacturer's and Design Specifications for System Components

### Septic Tank Specifications and Float Setting Details.






## Appendix C - Pump Specifications

### Myers Model ME50 (1/2 Hp) Selected

#### Product Capabilities

Capacities:	120 GPM	454 LPM
Shut-Off Head:	95 ft.	28.9 m
Max. Spherical Solids:	3/4 in.	19 mm
Liquids Handling:	domestic effluent and drain water	
Intermittent Liquid Temp.:	up to 140°F	up to 60°C
Motor Electrical Data:	1/2 HP, 115V, 1Ø, 1/2 to 1-1/2 HP, 230V, 1Ø, 208/230/460/575V, 3Ø, oil-filled, permanent split capacitor type, 1Ø, 3450 RPM, 60Hz	
Acceptable pH Range:	6–9	
Specific Gravity:	.9–1.1	
Viscosity:	28–35 SSU	
Discharge, NPT:	2 in.	50.8 mm
Housing:	cast iron	
Min. Sump Diameter:	Simplex Duplex	24 in. 36 in.
		61.0 cm 91.4 cm
Power Cord:	10 ft.	


Product Performance Chart




## Appendix D - Detailed System Schematics and Drawings

### TREATMENT FIELD PLAN

- Effluent Distribution Lateral piping = 1 in.
- Orifice spacing = 5 ft.
- Orifice dia. = 1/8 in.
- Actual chamber width in weeping lateral trench = 22 in.
- Weeping lateral trench depth = 18 to 24 in. below existing grade.



**Figure D1 - Detailed  
Field Layout Drawing  
(Plan View)**




**Figure D2: Pressure Distribution Lateral Layout Detail Drawing**

# ELEVATIONS & SYSTEM CROSS-SECTION

SCALE: Horiz 1"=5'

VERT. 1"=1'



## Appendix E – System Design Worksheets

### Primary Effluent Treatment Field

#### Trench Bottom Surface Area & Length Sizing

This design worksheet was developed by Alberta Municipal Affairs and Alberta Onsite Wastewater Management Association.

The complete system is to comply with Alberta Private Sewage Standard of Practice 2009  
This worksheet does NOT consider all of the requirements of the mandatory Standard  
Use only Imperial units of measurement throughout (feet, inches, Imperial gallons, etc...)

#### Step 1) Determine the expected volume of sewage per day:

Note: Use Table 2.2.2.2.A. (p.30) & 2.2.2.2.B. (p.31) as a guide to determine expected volume of sewage per day. Provide allowance for additional flow factors as detailed in Table 2.2.2.3. (p.32)

Expected Volume of Sewage per Day

461

F1

Assure that the sewage strength does not exceed the requirements of 2.2.2.1.(2) (p 30)  
Effluent quality must meet the requirement of Article 8.1.1.6(1)(a) page 97.

#### Step 2) Determine the (design) soil effluent loading rate:

Soil Effluent Loading Rate  
[From >30 - 150 mg/L column]

FSL

Texture

&

BK

Structure

&

3

Grade

=

0.32

Imp. gal/  
sq.ft./day

F2

Note: Effluent loading rate MUST be determined from soil texture, structure, and grade classification according to Imperial Table A.1.E.1. (p.151).

Note: Ensure infiltration loading rate chosen does not exceed loading rates as set out in 8.1.2.2. (p. 101)

#### Step 3) Calculate the required infiltration surface area for the soil BEFORE area reduction factors:

Expected Volume of Sewage  
per day

461

Imp. gal/day

From F1

÷

Soil Effluent  
Loading Rate

0.32

Imp. gal/sq. ft/day

From F2

=

Soil Infiltration Area  
Required

1441

sq.ft.

F3

At no time shall primary treated effluent loading rates  
exceed the loading rates for secondary treated effluent.

#### Step 4) Type and width of trench bottom used:

Actual Pipe & Rock Trench  
Width in inches.

inches

÷

12

=

feet

F4

Actual Chamber Width in  
inches

22

inches

÷

12

=

1.83

feet

F4A

**Step 5) Calculate optional credited loading rates for distribution systems:**

Primary treated effluent is required to have a minimum 5 feet Vertical Separation below infiltration zone.

					Credited Width of Trench (feet)	
Pipe & Rock Trench	<div> <div>Actual Width in Feet</div> <div>From F4</div> </div>	X	1	=	<div> <div>3 ft. Maximum</div> </div>	F5
Pipe & Rock Trench with Pressure Distribution	<div> <div>Actual Width in Feet</div> <div>From F4</div> </div>	X	1.2	=	<div> <div>3 ft. Maximum</div> </div>	F5
Chambers - Gravity Feed	<div> <div>Width of Chamber in Feet</div> <div>From F4A</div> </div>	X	1.1	=	<div> <div>3 ft. Maximum</div> </div>	F5A
Chambers - Pressure Distribution	<div> <div>1.83</div> <div>Width of Chamber in Feet</div> <div>From F4A</div> </div>	X	1.3	=	<div> <div>2.38</div> <div>3 ft. Maximum</div> </div>	F5B

**Step 6) Determine linear feet of trench required:**

Infiltration Area Required									
1441	sq. ft.	÷	2.38	ft.	=	605	feet		F6
From F3			From F5, F5A or F5B						

**Step 7) Select number of weeping lateral trenches and Determine length of each of trench:**

Total Trench Length Required in Field			Number of Individual Weeping Lateral Trenches			Length of Each Weeping Lateral Trench		
605	ft.	÷	5	=	120	feet		F8
From F6			F7 Designer Determination					

It is good practice to make the overall field area long and narrow when possible on a particular site.

**Step 8) Summary:**

F1	461	Imp. gal/day - Daily Flow, including any additional fixtures.
F2	0.32	Imp. gal/sq.ft. - Effluent Loading Rate.
F3	1441	Sq. Ft. - Soil Infiltration Surface Area.
F4 or F4A	1.83	Ft. - Actual width of Gravel Trench or Chamber.
F5, F5A or F5B	2.38	Ft. - Credited Width of Gravel Trench or Chambers.
F6	605	Ft. - Total trench length required.
F7	5	Number of weeping lateral trenches.
F8	120	Ft. - Length of each weeping lateral trench.

# Pressure Distribution, Orifice, Pipe & Pump Sizing

This design worksheet was developed by Alberta Municipal Affairs and  
Alberta Onsite Wastewater Management Association.

The completed installation is to comply with Alberta Private Sewage Standard of Practice 2009.

This worksheet is for use in Alberta to: size the orifices in distribution lateral pipes, size effluent delivery piping,  
and to calculate the required capacity and pressure head capability of the effluent pump.

It can be used for: calculating delivery of effluent to laterals in disposal fields, mounds and sand filters.

This worksheet does NOT consider all of the mandatory requirements of the Standard.

It is intended for use by persons having training in the private sewage discipline.

Note: Page numbers refer to the Private Sewage Systems Standard of Practice 2009.

Use only Imperial units of measurement throughout (feet, inches, Imperial gallons, etc...).

## Step 1) Select the pressure head to be maintained at the orifices:

Minimum pressure at the orifice:

3/16" or less orifice = 5 ft. Minimum - 2.6.2.5 (1), (p 48)

larger than 3/16" orifice = 2 ft. Minimum - 2.6.2.5 (1) (p 48)

Design pressure at lateral orifices

5

ft.

P1

*Note: worksheet will not provide an adequate design if laterals are at different elevations. Differing elevations will result in a different pressure head and volume of discharge at the orifices in each lateral. Additional considerations must be made f*

## Step 2) Select the size of orifice in the laterals:

Minimum size: 2.6.1.5. (1)(e) p. 46

1/8"

Orifice Diameter  
selected

1/8

in.

P2

Note: larger sizes are less likely to plug.

## Step. 3) Select the spacing of orifices and determine the number of orifices to be installed in distribution laterals:

Length of Distribution Lateral  
From system design drawings

Spacing of Orifices selected for  
design

Resulting number of orifices  
per lateral

60

ft.

÷

5

ft.

=

12

P3a

Select a spacing of orifices to attain even distribution over the treatment area:

Maximum spacings are determined for :

\* 5 ft. Primary treated effluent: 2.6.1.5 (e) (pp. 46 - 47)

\* 3 ft. Secondary treated effluent: 8.1.1.8 & 2.6.2.2 (c) (pp 98 & 47 - 48)

\* 3 ft. On sandy textured soils: 8.1.1.8 (p. 98)

12

X

10

=

120

P3b

From P3a

Number of Laterals

Total Number of Orifices All Laterals

*If laterals are of differing lengths, calculate each separately and add the number of orifices together.*

**Step 4) Determine the minimum pipe size of the distribution laterals:**

Enter the system design information into the 3 boxes below. If distribution laterals are of differing lengths, each lateral must be considered separately.

Orifice Diameter

**1/8**

in.

From P2

Length of Distribution Lateral

**60**

ft.

From System Design Drawings

Total Orifices Each Lateral

**12**

From P3a

Use Table A.1.A. (pp 140 - 143) when applying the information entered in this step to determine the minimum size of the distribution lateral pipe.

Size of Distribution Lateral Pipe

From Table A.1.A.

**1**

in.

P4

**Step 5) Determine the total flow from all orifices:**Total Number of  
Orifices in all laterals**120**

From P3b

**X**Gal/min for each Orifice  
at Head Pressure Selected**0.34**From Table A.1.B.  
(pp 144 & 145)Imp. gal  
/min.**=**Total flow from all lateral  
orifices**40.8**Imp. gal  
/min.

P5

**Step 6) Select the type and size of effluent delivery pipe:**

Use Tables A.1.C.1 to A.1.C.4 (pp 146 - 149) to aid in decision. A larger pipe will reduce pressure loss.

Type of pipe used for  
effluent delivery line**PVC**

Pipe size selected

**2**inch  
- NPS

P6

Choose a friction loss from Tables A.1.C.1 to A.1.C.4 in between the bolded lines to ensure a flow velocity between 2 to 5 feet per second. The pipe size selected will affect the amount of friction loss the pump must overcome to deliver effluent.

**Step 7) Calculate the equivalent length of pipe for pressure loss due to fittings:**

Insert total from Worksheet "A" on last page (p.5) of this Pressure Distribution Worksheet

Equivalent Length of All Fittings

**69.0**

ft.

P7

For Pressure Loss



**Step 8) Calculate the equivalent length of pipe from pump to the farthest end of header of distribution laterals for pressure loss:**

<b>Length of Piping (ft)</b> <div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">205</div>	+	<b>Equivalent Length of Fittings (ft)</b> <div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">69.0</div>	=	<b>Length of Pipe for Friction Loss (ft)</b> <div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">274</div>	P8
Length from pump to farthest end of distribution header supplying laterals.		Equivalent fitting length from P7.		Used to determine total pressure head loss due to friction loss in piping.	

**Step 9) Calculate the pressure head loss in delivery pipe including fittings:**

<b>Total Length of Pipe for Friction Loss</b> <div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">274</div>	Divide by 100 ft. x	<b>Friction Loss per 100 feet of pipe</b> <div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">3.7</div>	ft.	=	<b>Delivery Piping Pressure Head Loss</b> <div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">10.1</div>	ft.	P9
From P8		Use Tables A.1.C. On pp 146 - 150 using flow volume from P5.					

Don't forget to divide the length by 100 feet to match the factors in the tables.

**Step 10) Calculate the total pressure head required at pump:**

Delivery piping pressure loss	+	<div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">10.1</div>	ft.	From P9
Lift distance of effluent from effluent level in tank to orifices	+	<div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">7</div>	ft.	Measure from lowest effluent level in tank to elevation of orifices.
Design pressure at orifices	+	<div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">5</div>	ft.	From P1
Head loss allowed if an inline filter is used in pressure piping	+	<div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">5.48</div>	ft.	<b>Explain Pressure Loss Allowed if Applied</b> <div style="border: 1px solid black; padding: 5px; width: 250px; margin: 10px auto;">A pressure loss of 0.48 ft across filter and 5 ft until alarm goes off.</div>
Add 1 ft to allow for pressure loss along the distribution lateral	+	<div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">1</div>	ft.	
<b>Total minimum pressure head pump must provide at Imp. gal/min required to supply orifices</b>		<div style="border: 1px solid black; padding: 5px; width: 150px; margin: 10px auto;">28.6</div>	ft.	P10

Step 11) Select the size of the drain back orifice if used and determine the flow from the drain back orifice. Then calculate total flow requirement for pump:

Size of Drain Back Orifice	Determine flow using Head Pressure at Drain Back Orifice	Flow from all lateral orifices	Total Imp. Gallons per Minute from the pump	
<b>1/4</b> in.	<b>3.3</b> Imp. gal /min Use pressure head from P10 to find flow from Extended Table A.1.B.1	<b>40.8</b> Imp. gal /min From P5	<b>44.1</b> Imp. gal /min	P11

Step 12) Details of the pump specifications required:

Required Flow Rate (Imp. gal/min)		Required Pressure Head (ft)
<b>44.1</b>	@	<b>28.6</b>
From P11		From P10
Imp. gal (P11) multiplied by 1.2 = U.S. gallons		Required Flow Rate (US gal/min)
		<b>52.9</b>

Select the appropriate pump by reviewing the pump curve of available pumps. Select a pump that exceeds the requirements set out in this step by approximately 10% considering both pressure head and volume.

Step 13) Consider the pumping demands of the system. If they are considered excessive, redesign the pressure distribution system and recalculate the pump demands.

**Worksheet "Appendix A" Determine Equivalent Length of Pipe due to fittings in piping system.**

Determine the equivalent length of pipe to allow for friction loss due to fittings in the piping system:

	Number of Fittings		Friction loss as per Table A.1.C.5 or 6 (p. 150)		Total
90° Elbows	5	X	5.7	=	28.5
					+
45° Elbows		X		=	
					+
Gate and Ball Valves		X		=	
					+
Tee-on- Branch (TOB)	3	X	12.0	=	36.0
					+
Tee-on-Runs (TOR)		X		=	
					+
Male Iron pipe Adaptors (M/F Threaded Adaptors)	1	X	4.5	=	4.5
					=
Total Equivalent Length of pipe to allow for fittings in piping system			(Enter this total, Box P7)		69.0

# Primary Effluent Treatment Field

## Trench Bottom Surface Area & Length Sizing

This design worksheet was developed by Alberta Municipal Affairs and  
Alberta Onsite Wastewater Management Association.

The complete system is to comply with Alberta Private Sewage Standard of Practice 2009

This worksheet does NOT consider all of the requirements of the mandatory Standard

Use only Imperial units of measurement throughout (feet, inches, Imperial gallons, etc...)

### Step 1) Determine the expected volume of sewage per day:

Note: Use Table 2.2.2.2.A. (p.30) & 2.2.2.2.B. (p.31) as a guide to determine expected volume of sewage per day. Provide allowance for additional flow factors as detailed in Table 2.2.2.3. (p.32)

Expected Volume of Sewage per  
Day

F1

Assure that the sewage strength does not exceed the requirements of 2.2.2.1.(2) (p 30)  
Effluent quality must meet the requirement of Article 8.1.1.6(1)(a) page 97.

### Step 2) Determine the design soil effluent loading rate:

Soil Effluent Loading Rate  
[From >30 - 150 mg/L column]

Texture

&

Structure

&

Grade

=

Imp. gal/  
sq.ft./day

F2

Note: Effluent loading rate MUST be determined from soil texture, structure, and grade classification according to Imperial Table A.1.E.1. (p.151).

Note: Ensure infiltration loading rate chosen does not exceed loading rates as set out in 8.1.2.2. (p. 101).

### Step 3) Calculate the required infiltration surface area for the soil BEFORE area reduction factors:

Expected Volume of Sewage  
per day

Imp. gal/day

From F1

÷

Soil Effluent  
Loading Rate

Imp. gal/sq. ft/day

From F2

=

Soil Infiltration Area  
Required

sq.ft.

F3

At no time shall primary treated effluent loading rates  
exceed the loading rates for secondary treated effluent.

### Step 4) Type and width of trench bottom used:

Actual Pipe & Rock Trench  
Width in inches.

inches

÷

12

=

feet

F4

Actual Chamber Width in  
inches

inches

÷

12

=

feet

F4A

**Step 5) Calculate optional credited loading rates for distribution systems:**

Primary treated effluent is required to have a minimum 5 feet Vertical Separation below infiltration zone.

					Credited Width of Trench (feet)	
Pipe & Rock Trench	<div>Actual Width in Feet</div> <div>From F4</div>	X	1	=	<div>3 ft. Maximum</div>	F5
Pipe & Rock Trench with Pressure Distribution	<div>Actual Width in Feet</div> <div>From F4</div>	X	1.2	=	<div>3 ft. Maximum</div>	F5
Chambers - Gravity Feed	<div>Width of Chamber in Feet</div> <div>From F4A</div>	X	1.1	=	<div>3 ft. Maximum</div>	F5A
Chambers - Pressure Distribution	<div>Width of Chamber in Feet</div> <div>From F4A</div>	X	1.3	=	<div>3 ft. Maximum</div>	F5B

**Step 6) Determine linear feet of trench required:**

<b>Infiltration Area Required</b>		<b>Credited Width of Trench</b>		<b>Total Trench Length in Field</b>	
<div>sq. ft.</div>	÷	<div>ft.</div>	=	<div>feet</div>	F6
From F3		From F5, F5A or F5B			

**Step 7) Select number of weeping lateral trenches and Determine length of each of trench:**

<b>Total Trench Length Required in Field</b>		<b>Number of Individual Weeping Lateral Trenches</b>		<b>Length of Each Weeping Lateral Trench</b>	
<div>ft.</div>	÷		=	<div>feet</div>	F8
From F6		F7 Designer Determination			

It is good practice to make the overall field area long and narrow when possible on a particular site.

**Step 8) Summary:**

F1		Imp. gal/day - Daily Flow, including any additional fixtures.
F2		Imp. gal/sq.ft. - Effluent Loading Rate.
F3		Sq. Ft. - Soil Infiltration Surface Area.
F4 or F4A		Ft. - Actual width of Gravel Trench or Chamber.
F5, F5A or F5B		Ft. - Credited Width of Gravel Trench or Chambers.
F6		Ft. - Total trench length required.
F7		Number of weeping lateral trenches.
F8		Ft. - Length of each weeping lateral trench.

# Primary Effluent Treatment Field

## Trench Bottom Surface Area & Length Sizing

This design worksheet was developed by Alberta Municipal Affairs and  
Alberta Onsite Wastewater Management Association.

The complete system is to comply with Alberta Private Sewage Standard of Practice 2009

This worksheet does NOT consider all of the requirements of the mandatory Standard

Use only Imperial units of measurement throughout (feet, inches, Imperial gallons, etc...)

### Step 1) Determine the expected volume of sewage per day:

Note: Use Table 2.2.2.2.A. (p.30) & 2.2.2.2.B. (p.31) as a guide to determine expected volume of sewage per day. Provide allowance for additional flow factors as detailed in Table 2.2.2.3. (p.32)

Expected Volume of Sewage per  
Day

F1

Assure that the sewage strength does not exceed the requirements of 2.2.2.1.(2) (p 30)  
Effluent quality must meet the requirement of Article 8.1.1.6(1)(a) page 97.

### Step 2) Determine the design soil effluent loading rate:

Soil Effluent Loading Rate  
[From >30 - 150 mg/L column]

Texture

&

Structure

&

Grade

=

Imp. gal/  
sq.ft./day

F2

Note: Effluent loading rate MUST be determined from soil texture, structure, and grade classification according to Imperial Table A.1.E.1. (p.151).

Note: Ensure infiltration loading rate chosen does not exceed loading rates as set out in 8.1.2.2. (p. 101).

### Step 3) Calculate the required infiltration surface area for the soil BEFORE area reduction factors:

Expected Volume of Sewage  
per day

Imp. gal/day

From F1

÷

Soil Effluent  
Loading Rate

Imp. gal/sq. ft/day

From F2

=

Soil Infiltration Area  
Required

sq.ft.

F3

At no time shall primary treated effluent loading rates  
exceed the loading rates for secondary treated effluent.

### Step 4) Type and width of trench bottom used:

Actual Pipe & Rock Trench  
Width in inches.

inches

÷

12

=

feet

F4

Actual Chamber Width in  
inches

inches

÷

12

=

feet

F4A

**Step 5) Calculate optional credited loading rates for distribution systems:**

Primary treated effluent is required to have a minimum 5 feet Vertical Separation below infiltration zone.

					Credited Width of Trench (feet)	
Pipe & Rock Trench	<div> <div></div> <div>Actual Width in Feet From F4</div> </div>	X	<div> <div>1</div> </div>	=	<div> <div></div> <div>3 ft. Maximum</div> </div>	F5
Pipe & Rock Trench with Pressure Distribution	<div> <div></div> <div>Actual Width in Feet From F4</div> </div>	X	<div> <div>1.2</div> </div>	=	<div> <div></div> <div>3 ft. Maximum</div> </div>	F5
Chambers - Gravity Feed	<div> <div></div> <div>Width of Chamber in Feet From F4A</div> </div>	X	<div> <div>1.1</div> </div>	=	<div> <div></div> <div>3 ft. Maximum</div> </div>	F5A
Chambers - Pressure Distribution	<div> <div></div> <div>Width of Chamber in Feet From F4A</div> </div>	X	<div> <div>1.3</div> </div>	=	<div> <div></div> <div>3 ft. Maximum</div> </div>	F5B

**Step 6) Determine linear feet of trench required:**

Infiltration Area Required		Credited Width of Trench		Total Trench Length in Field	
<div></div>	sq. ft.	÷	<div></div> ft.	=	<div></div> feet
From F3			From F5, F5A or F5B		F6

**Step 7) Select number of weeping lateral trenches and Determine length of each of trench:**

Total Trench Length Required in Field		Number of Individual Weeping Lateral Trenches		Length of Each Weeping Lateral Trench	
<div></div>	ft.	÷	<div></div>	=	<div></div> feet
From F6			F7 Designer Determination		F8

It is good practice to make the overall field area long and narrow when possible on a particular site.

**Step 8) Summary:**

F1		Imp. gal/day - Daily Flow, including any additional fixtures.
F2		Imp. gal/sq.ft. - Effluent Loading Rate.
F3		Sq. Ft. - Soil Infiltration Surface Area.
F4 or F4A		Ft. - Actual width of Gravel Trench or Chamber.
F5, F5A or F5B		Ft. - Credited Width of Gravel Trench or Chambers.
F6		Ft. - Total trench length required.
F7		Number of weeping lateral trenches.
F8		Ft. - Length of each weeping lateral trench.

# Pressure Distribution, Orifice, Pipe & Pump Sizing

This design worksheet was developed by Alberta Municipal Affairs and  
Alberta Onsite Wastewater Management Association.

The completed installation is to comply with Alberta Private Sewage Standard of Practice 2009.

This worksheet is for use in Alberta to: size the orifices in distribution lateral pipes, size effluent delivery piping,  
and to calculate the required capacity and pressure head capability of the effluent pump.

It can be used for: calculating delivery of effluent to laterals in disposal fields, mounds and sand filters.

This worksheet does NOT consider all of the mandatory requirements of the Standard.

It is intended for use by persons having training in the private sewage discipline.

Note: Page numbers refer to the Private Sewage Systems Standard of Practice 2009.

Use only Imperial units of measurement throughout (feet, inches, Imperial gallons, etc...).

## Step 1) Select the pressure head to be maintained at the orifices:

Minimum pressure at the orifice:

3/16" or less orifice = 5 ft. Minimum - 2.6.2.5 (1), (p 48)

larger than 3/16" orifice = 2 ft. Minimum - 2.6.2.5 (1) (p 48)

Design pressure at lateral orifices

ft.

P1

*Note: worksheet will not provide an adequate design if laterals are at different elevations. Differing elevations will result in a different pressure head and volume of discharge at the orifices in each lateral. Additional considerations must be made for laterals at differing elevations.*

## Step 2) Select the size of orifice in the laterals:

Minimum size: 2.6.1.5. (1)(e) p. 46

1/8"

Orifice Diameter  
selected

in.

P2

*Note: larger sizes are less likely to plug.*

## Step. 3) Select the spacing of orifices and determine the number of orifices to be installed in distribution laterals:

Length of Distribution Lateral  
From system design drawings

Spacing of Orifices selected for  
design

Resulting number of orifices  
per lateral

ft.

÷

ft.

=

P3a

Select a spacing of orifices to attain even distribution over the treatment area:

Maximum spacings are determined for :

\* 5 ft. Primary treated effluent: 2.6.1.5 (e) (pp. 46 - 47)

\* 3 ft. Secondary treated effluent: 8.1.1.8 & 2.6.2.2 (c) (pp 98 & 47 - 48)

\* 3 ft. On sandy textured soils: 8.1.1.8 (p. 98)

From P3a

X

Number of Laterals

=

Total Number of Orifices All Laterals

P3b

*If laterals are of differing lengths, calculate each separately and add the number of orifices together.*



**Step 4) Determine the minimum pipe size of the distribution laterals:**

Enter the system design information into the 3 boxes below. If distribution laterals are of differing lengths, each lateral must be considered separately.

**Orifice Diameter**

in.

From P2

**Length of Distribution Lateral**

ft.

From System Design Drawings

**Total Orifices Each Lateral**

From P3a

Use Table A.1.A. (pp 140 - 143) when applying the information entered in this step to determine the minimum size of the distribution lateral pipe.

**Size of Distribution Lateral Pipe**  
From Table A.1.A.

in.

P4

**Step 5) Determine the total flow from all orifices:****Total Number of  
Orifices in all laterals**

From P3b

**X****Gal/min for each Orifice  
at Head Pressure Selected**From Table A.1.B.  
(pp 144 & 145)Imp. gal  
/min.**=****Total flow from all lateral  
orifices**Imp. gal  
/min.

P5

**Step 6) Select the type and size of effluent delivery pipe:**

Use Tables A.1.C.1 to A.1.C.4 (pp 146 - 149) to aid in decision. A larger pipe will reduce pressure loss.

**Type of pipe used  
for effluent delivery****Pipe size selected**inch  
- NPS

P6

Choose a friction loss from Tables A.1.C.1 to A.1.C.4 in between the bolded lines to ensure a flow velocity between 2 to 5 feet per second. The pipe size selected will affect the amount of friction loss the pump must overcome to deliver effluent.

**Step 7) Calculate the equivalent length of pipe for pressure loss due to fittings:**

Insert total from Worksheet "A" on last page (p.5) of this Pressure Distribution Worksheet

**Equivalent Length of All Fittings**

ft.

P7

For Pressure Loss

**Step 8) Calculate the equivalent length of pipe from pump to the farthest end of header of distribution laterals for pressure loss:**

<b>Length of Piping (ft)</b> <div style="border: 1px solid black; height: 40px; width: 100%;"></div>	+	<b>Equivalent Length of Fittings (ft)</b> <div style="border: 1px solid black; height: 40px; width: 100%;"></div>	=	<b>Length of Pipe for Friction Loss (ft)</b> <div style="border: 1px solid black; height: 40px; width: 100%;"></div>	P8
Length from pump to farthest end of distribution header supplying laterals.		Equivalent fitting length from P7.		Used to determine total pressure head loss due to friction loss in piping.	

**Step 9) Calculate the pressure head loss in delivery pipe including fittings:**

<b>Total Length of Pipe for Friction Loss</b> <div style="border: 1px solid black; height: 40px; width: 100%; text-align: center;">           Divide by 100 ft.         </div>	X	<b>Friction Loss per 100 feet of pipe</b> <div style="border: 1px solid black; height: 40px; width: 100%;"></div>	ft.	=	<b>Delivery Piping Pressure Head Loss</b> <div style="border: 1px solid black; height: 40px; width: 100%;"></div>	ft.	P9
From P8		Use Tables A.1.C. On pp 146 - 150 using flow volume from P5.			Don't forget to divide the length by 100 feet to match the factors in the tables.		

**Step 10) Calculate the total pressure head required at pump:**

Delivery piping pressure loss	+	<div style="border: 1px solid black; height: 30px; width: 100%;"></div>	ft.	From P9
Lift distance of effluent from effluent level in tank to orifices	+	<div style="border: 1px solid black; height: 30px; width: 100%;"></div>	ft.	Measure from lowest effluent level in tank to elevation of orifices.
Design pressure at orifices	+	<div style="border: 1px solid black; height: 30px; width: 100%;"></div>	ft.	From P1
Head loss allowed if an inline filter is used in pressure piping	+	<div style="border: 1px solid black; height: 30px; width: 100%;"></div>	ft.	<b>Explain Pressure Loss Allowed if Applied</b> <div style="border: 1px solid black; height: 30px; width: 100%;"></div>
Add 1 ft to allow for pressure loss along the distribution lateral	+	<div style="border: 1px solid black; height: 30px; width: 100%;"></div>	ft.	
<b>Total minimum pressure head pump must provide at Imp. gal/min required to supply orifices</b>		<div style="border: 1px solid black; height: 30px; width: 100%;"></div>	ft.	P10

**Step 11) Select the size of the drain back orifice if used and determine the flow from the drain back orifice. Then calculate total flow requirement for pump:**

<b>Size of Drain Back Orifice</b>	<b>Determine flow using Head Pressure at Drain Back Orifice</b>	<b>Flow from all lateral orifices</b>	<b>Total Imp. Gallons per Minute from the pump</b>			
<div style="border: 1px solid black; width: 80px; height: 30px; margin: 0 auto;"></div> in.	<div style="border: 1px solid black; width: 80px; height: 30px; margin: 0 auto;"></div> Imp. gal /min  Use pressure head from P10 to find flow from Extended Table A.1.B.1	+ <div style="border: 1px solid black; width: 80px; height: 30px; margin: 0 auto;"></div> Imp. gal /min  From P5	= <div style="border: 1px solid black; width: 150px; height: 30px; margin: 0 auto;"></div> Imp. gal /min	P11		

**Step 12) Details of the pump specifications required:**

<b>Required Flow Rate (Imp. gal/min)</b>  <div style="border: 1px solid black; width: 150px; height: 30px; margin: 0 auto;"></div> From P11	@	<b>Required Pressure Head (ft)</b>  <div style="border: 1px solid black; width: 150px; height: 30px; margin: 0 auto;"></div> From P10	Select the appropriate pump by reviewing the pump curve of available pumps. Select a pump that exceeds the requirements set out in this step by approximately 10% considering both pressure head and volume.
Imp. gal (P11) multiplied by 1.2 = U.S. gallons		<b>Required Flow Rate (US gal/min)</b>  <div style="border: 1px solid black; width: 150px; height: 30px; margin: 0 auto;"></div>	

**Step 13) Consider the pumping demands of the system. If they are considered excessive, redesign the pressure distribution system and recalculate the pump demands.**

**Worksheet "Appendix A" Determine Equivalent Length of Pipe due to fittings in piping system.**

Determine the equivalent length of pipe to allow for friction loss due to fittings in the piping system:

	Number of Fittings		Friction loss as per Table A.1.C.5 or 6 (p. 150)		Total
90° Elbows	<input type="text"/>	X	<input type="text"/>	=	<input type="text"/>
					+
45° Elbows	<input type="text"/>	X	<input type="text"/>	=	<input type="text"/>
					+
Gate and Ball Valves	<input type="text"/>	X	<input type="text"/>	=	<input type="text"/>
					+
Tee-on- Branch (TOB)	<input type="text"/>	X	<input type="text"/>	=	<input type="text"/>
					+
Tee-on-Runs (TOR)	<input type="text"/>	X	<input type="text"/>	=	<input type="text"/>
					+
Male Iron pipe Adaptors (M/F Threaded Adaptors)	<input type="text"/>	X	<input type="text"/>	=	<input type="text"/>
					=
Total Equivalent Length of pipe to allow for fittings in piping system			(Enter this total, Box P7)		<input type="text"/>

# Alberta Private Sewage Treatment System Soil Profile Log Form

Owner Name or Job ID.

Legal Land Location										Test Pit GPS Coordinates		
LSD-1/4	Sec	Twp	Rg	Mer	Lot	Block	Plan	Easting	Northing			
Vegetation notes:										Overall site slope %		
Slope position of test pit:												
Test hole No.		Soil Subgroup		Parent Material		Drainage		Depth of Lab sample #1		Depth of Lab sample #2		
Horizon	Depth (cm) (in)	Texture	Lab or HT	Colour	Gleying	Mottling	Structure	Grade	Consistence	Moisture	% Coarse Fragments	
Depth to Groundwater				Restricting Soil Layer Characteristic								
Depth to Seasonally Saturated Soil				Depth to restrictive Soil Layer								
Site Topography				Depth to Highly Permeable Layer Limiting Design								
Key Soil Characteristics applied to system design effluent loading												
Weather Condition notes:												
Comments: such as root depth and abundance or other pertinent observations:												

Alberta Private Sewage Treatment System Soil Profile Log Form

Owner Name or Job ID.

Legal Land Location										Test Pit GPS Coordinates		
LSD-1/4		Sec	Twp	Rg	Mer	Lot	Block	Plan	Easting	Northing		
Vegetation notes:										Overall site slope %		
										Slope position of test pit:		
Test hole No.		Soil Subgroup			Parent Material		Drainage	Structure	Grade	Consistence	Moisture	% Coarse Fragments
Horizon	Depth (cm) (in)	Texture	Lab or HT	Colour	Gleying	Mottling	Structure	Grade	Consistence	Moisture	% Coarse Fragments	
Depth to Groundwater		Restricting Soil Layer Characteristic										
Depth to Seasonally Saturated Soil		Depth to restrictive Soil Layer										
Site Topography		Depth to Highly Permeable Layer Limiting Design										
Key Soil Characteristics applied to system design effluent loading												
Weather Condition notes:												
Comments: such as root depth and abundance or other pertinent observations:												

Onsite Sewage System Site Evaluation Lot Diagram Field Sketch and Notes

Project Name:

Lot or Legal Description:

Date:


<div><div>↑N</div></div>													<div>Show the proposed location of the onsite sewage system and the following items indicating their distances from the proposed system:</div> <div>trees</div> <div>floodplains</div> <div>wells</div> <div>water sources</div> <div>surface water</div> <div>bedrock</div> <div>outcrops</div> <div>buildings</div> <div>property lines</div> <div>easement lines</div> <div>ditches or</div> <div>interceptors</div> <div>banks or steep slopes</div> <div>fills</div> <div>driveways</div> <div>existing sewage systems</div> <div>underground utilities</div> <div>soil test pit and borehole locations</div>
<div>drainage course</div> <div></div>		<div>slope direction</div> <div></div>		<div>borehole</div> <div>BH 1 </div>		<div>Test Pit</div> <div>P1 </div>							

Comments:

Property line GPS coordinates:  
GPS coordinates of well:  
GPS coordinate of tank:  
GPS coordinates of soil treatment component corners:

Additional information is required separately for the system design detail.

**Figure 4: Diagrammatic representation of soil structure**



**SLOPE CLASSES OF LOCAL LANDFORMS**

Slope Class	Percent Slope	Approximate Degrees	Description
1	0-0.5	0	level
2	0.5-2.5	0.3-1.5	nearly level
3	2-5	1-3	very gentle slopes
4	6-9	3.5-5	gentle slopes
5	10-15	6-8.5	moderate slopes
6	16-30	9-17	strong slopes
7	31-45	17-24	very strong slopes
8	46-70	25-35	extreme slopes
9	71-100	35-45	steep slopes
10	>100	>45	very steep slopes

**SURFACE STONINESS**

	Surface Area	Distance Apart (cm)
S0 non-stony	<0.01%	>30
S1 slightly stony	0.01-0.1%	10-30
S2 moderately stony	0.1-3%	2-10
S3 very stony	3-15%	1-2
S4 exceedingly stony	15-50%	0.1-5
S5 excessively stony	50%	0.1

**SLOPE POSITION**

c	- crest
u	- upper slope
m	- mid slope
l	- lower slope
t	- toe
d	- depression
l	- level

**DRAINAGE**

VR	- very rapidly
R	- rapidly
w	- well
M	- moderately well
I	- imperfectly
P	- poorly
VP	- very poorly






Table 10. Types, kinds and classes of soil structure.

Type	Kind (Kind Code)	Structure Class and Code	Size <sup>1</sup> (mm)
<b>Blocklike</b> - soil particles arranged around a point and bounded by flat or rounded surfaces <b>BK</b>	<b>Angular blocky (ABK)</b> peds bounded by flattened, rectangular faces intersecting at relatively sharp angles	<b>VF:</b> very fine angular blocky <b>F:</b> fine angular blocky <b>M:</b> medium angular blocky <b>C:</b> coarse angular blocky <b>VC:</b> very coarse angular blocky	<5 5-10 10-20 20-50 >50
	<b>Subangular blocky (SBK):</b> peds bounded by slightly rounded, subrectangular faces with vertices <sup>2</sup> of their intersections mostly subrounded	<b>VF:</b> very fine subangular blocky <b>F:</b> fine subangular blocky <b>M:</b> medium subangular blocky <b>C:</b> coarse subangular blocky <b>VC:</b> very coarse subangular blocky	<5 5-10 10-20 20-50 >50
	<b>Granular (GR):</b> spheroidal peds bounded by curved or very irregular faces that do not adjoin those of adjacent peds	<b>VF:</b> very fine granular <b>F:</b> fine granular <b>M:</b> medium granular <b>C:</b> coarse granular <b>VC:</b> very coarse granular	<1 1-2 2-5 5-10 >10
<b>Platelike:</b> soil particles arranged around a horizontal plane and generally bounded by relatively flat horizontal surfaces <b>PL</b>	<b>Platy (PL):</b> peds flat or platelike; horizontal planes more or less well developed	<b>VF:</b> very fine platy <b>F:</b> fine platy <b>M:</b> medium platy <b>C:</b> coarse platy <b>VC:</b> very coarse platy	<1 1-2 2-5 5-10 >10
	<b>Prismatic (PR):</b> vertical faces of peds well defined and vertices <sup>2</sup> angular (edges sharp); prism tops essentially flat	<b>VF:</b> very fine prismatic <b>F:</b> fine prismatic <b>M:</b> medium prismatic <b>C:</b> coarse prismatic <b>VC:</b> very coarse prismatic	<10 10-20 20-50 50-100 >100
	<b>Columnar (COL):</b> vertical edges near top of columns not sharp (vertices <sup>2</sup> subrounded); column tops flat, rounded, or irregular	<b>VF:</b> very fine columnar <b>F:</b> fine columnar <b>M:</b> medium columnar <b>C:</b> coarse columnar <b>VC:</b> very coarse prismatic	<10 10-20 20-50 50-100 >100
<b>Structureless:</b> no observable aggregation of primary particles or no definite orderly arrangement around natural lines of weakness <b>MA</b>	<b>Single grained (SGR):</b>  <b>Massive (MA):</b>	Loose, incoherent mass of individual primary particles, as in sands  amorphous; a coherent mass showing no evidence of any distinct arrangement of soil particles; separates into clusters of particles; not peds	
<b>Cloddy (CDY):</b> not a structure; used to indicate the condition of some ploughed surface, grade, class, and shape too varied to be described in standard terms.			

<sup>1</sup> The size limits refer to measurements in the smallest dimension of platy, prismatic, and columnar peds and to the largest of the nearly equal dimensions of blocky and granular peds.

<sup>2</sup> Definition of vertex (plural, vertices): the intersection of two planes of a geometrical figure.

Consistence – moist soil	
• Loose:	No intact sample can be obtained.
• Friable:	Structure breaks down with slight force between the fingers.
• Firm:	Structure breaks down with moderate force between the fingers.
• Extremely firm:	Structure breaks down with moderate force between the hands or slight foot pressure.
• Rigid:	Structure breaks down only with foot pressure.

## Structure Grade Descriptions

Code	Structure Grade Definition	
0	<b>Massive /or single grained used to describe sands</b>	This describes a soil that has no developed structure. There is no aggregation of primary particles or no definite orderly arrangement around natural lines of weakness.
1	<b>Weak</b>	Peds are either indistinct and barely evident in place, or observable in place but incompletely separated from adjacent peds. When disturbed, the soil material separates into a mixture of only a few entire peds, many broken peds and much unaggregated material.
2	<b>Moderate</b>	Peds are moderately durable, and are evident but not distinct in the undisturbed soil. When disturbed, the soil material parts into a mixture of many well formed, entire peds, some broken peds, and little unaggregated material. The peds may be handled without breaking and they part from adjoining peds to reveal nearly entire surfaces which have properties distinct from those caused by fracturing.
3	<b>Strong</b>	Peds are durable and evident in the undisturbed soil, adhere weakly to one another, withstand displacement and separate cleanly when the soil is disturbed. When removed, the soil material separates mainly into entire peds. Surfaces of unbroken peds have distinctive properties, compared to surfaces that result from fracturing.

## Mottling Descriptions

Parameter	Code	Description
<b>Abundance</b>	<b>Few</b>	<2% of the exposed surface
	<b>Common</b>	2-20% of the exposed surface
	<b>Many</b>	>20% of the exposed surface
<b>Size</b>	<b>Fine</b>	< 5 mm
	<b>Medium</b>	5-15 mm
	<b>Coarse</b>	>15 mm
<b>Contrast</b>	<b>Faint</b>	Evident only on close examination. Faint mottles commonly have the same hue as the colour to which they are compared and differ by no more than 1 unit of chroma or 2 units of value. Some faint mottles of similar but low chroma and value can differ by 2.5 units of hue.
	<b>Distinct</b>	Readily seen, but contrast only moderately with the colour to which they are compared. Distinct mottles commonly have the same hue as the colour to which they are compared, but differ by 2 to 4 units of chroma or 3 to 4 units of value; or differ from the colour to which they are compared by 2.5 units of hue but by no more than 1 unit of chroma or 2 units of value.
	<b>Prominent</b>	Contrast strongly with the colour to which they are compared. Prominent mottles are commonly the most obvious colour feature in a soil. Prominent mottles that have medium chroma and value commonly differ from the colour to which they are compared by at least 5 units of hue if chroma and value are the same; or at least 1 unit of chroma or 2 units of value if hue differs by 2.5 units.

**Taste Test  
Stickiness Test  
Worm Test**

**Moist  
Cast Test**

**Graininess Test  
(Organic Matter Test)**

**Moist Cast Test  
Stickiness Test**

**Taste Test  
Worm Test**

